SUBJECT: Maximum gas pipe installation without air test

EFFECTIVE DATE: October 25, 2010

INTERPRETATION NUMBER: ADM – 2.1204.4

SEE ALSO: 2006 UPC – Section 1204.4

INTERPRETATION SUMMARY

Staff has determined that air testing of gas pipe shall be mandatory for all gas piping that will be concealed, including crawl spaces and attics, no matter how minor. Screwed gas pipe up to 20' in developed length and containing no more that 5 fittings or valves in unconcealed locations shall not be required to be air tested.